

Form GP-3
Rev. 6-26-62

16
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1963
Sep 24, 1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drg Co & Whitestone Pet
Complete Address: Box 797 Great Bend, Kansas
Lease Name Russ Well No. 1
Location NE SE SE Sec. 35 Twp. 8 Rge. (E) (W) 18
County Rooks Total Depth 3534
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: same
Address: License No.
Operation Completed: Hour 9AM Day 22 Month 9 Year 63

The Above well was plugged as follows:

8 5/8" 204' circulated with cement.
Circulated hole with heavy mud, set plug at 550', displaced 20 sax cement
through drill pipe, heavy mud to 180', set plug, 1/3 sack hulls and displaced
20 sax cement through dfill pipe, heavy mud to 35', set plug, 1/2 sack
hulls and filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/24/63
INV. NO. 4981-W

Signed: *Leon Perry*
Well-Plugging Supervisor