

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 10 1976
MAR 10, 1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163-20,604 -00-00 (of this well)

Operator's Full Name A. L. Abercrombie, Inc.
Complete Address 801 Union Center, Wichita, Kansas
Lease Name Radke Well No. 2
Location SE NW NW Sec. 35 Twp. 8 Rge. (E) (W) 18
County Rooks Total Depth 3470'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 1:15 P Day 9 Month 3 Year 1976

The above well was plugged as follows:

RTD 3470' 8 5/8 csg set 214' cwc 150 sx. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 285' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-10-76

INV. NO. 2877-W

Signed: Leo Massey
Well Plugging Supervisor