

15-163-03724-00-8

Form CP-3
Rev. 6-4-68

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name K & G Oil Company
Complete Address Drawer 368 Plainville, Kansas 67663
Lease Name Toepffer Well No. 1
Location C NE SE Sec. 36 Twp. 8 Rge. (E) (W) 18
County Rooks Total Depth 3439
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Go. Tools by HOWCO
Address _____ License No. _____

Operation Completed: Hour 3:30 P Day 5 Month 5 Year 1971

The above well was plugged as follows:

- Total Depth 3439' 8 5/8 csg set at 42' cwc
- 4 1/2 csg set at 3417' cw 100 sk cmt.
- 4 1/2 csg PBTB 3340' and perf. (3293-3346) Dakato squeezed and circ. with 900 sk cmt.
- Circ. 10 sk gel -set 50 sk cmt plug (2680-3340)
- Displaced 70 sk cmt (350-1250)
- Set 5 sk cmt plug (175-250) & 5 sk cmt plug (0-50)
- All plugs set thru tubing by HOWCO pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/13/71
INV. NO. 3672-W

Signed: Leo F. Massey
Well Plugging Supervisor