

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 07 1978
Feb 07, 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,766 -00 -a (of this well)

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill, Plainville, Kansas

Lease Name Mosher Well No. 1

Location NE SW Sec. 33 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Pioneer Drlg.

Address Plainville, Kansas License No.

Operation Completed: Hour 5:30 P Day 4 Month 2 Year 1978

The above well was plugged as follows:

RTD 3450' 8 5/8 csg. set 253' cwc 160 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-8-78

INV. NO. 6718-W

Signed: Leo Massey
Well Plugging Supervisor