

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-20-773 0300

LEASE NAME Dopita J

WELL NUMBER # 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 31 TWP. 8 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 2-22-78

Plugging Commenced 3-27-97

Plugging Completed 3-27-97

LEASE OPERATOR Viola Brown dba Kenny Brown Enterprises

ADDRESS P O Drawer 340

PHONE# (913) 434-7236 OPERATORS LICENSE NO. 5537

Character of Well \_\_\_\_\_

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 26-97 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filled? unknown If not, is well log attached? yes

Producing Formation Kansas City Depth to Top 3311 Bottom 3377 T.D. 3471'

Show depth and thickness of all water, oil and gas formations.

PBTD: 3444'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	top	171'	8 5/8"	171'	0
	production	top	3469	5 1/2"	3469'	0
	tubing			2 3/4"	34444'	19 00'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section.

tubing set @ 1900' pumped in 100 sk cement, 300# hull, 300# psi

tubing set @ 1000' pumped in 50 sk down braden head 20# psi

tubing set @ 450' pumped in 100 sk cement 200# hulls cement circulated to surface

(see attached Halliburton invoice) total cement-250 sks, 10% gel, 500# hulls

Name of Plugging Contractor Halliburton Services

License No. \_\_\_\_\_

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kenny Brown Enterprises

STATE OF Kansas COUNTY OF Rooks, ss.

Viola Brown-operator

(Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed in  
the same are true and correct, so help me God.

(Signature) Viola E Brown

(Address) Hainville, Ks 67663

SUBSCRIBED AND SWORN TO before me this 28<sup>th</sup> day of March, 19 97

Barbara West

NOTARY PUBLIC - State of Kansas  
BARBARA WEST  
My Appt. Exp. 5-27-99

My Commission Expires:  
USE ONLY ONE SIDE OF EACH FORM

15-163-20773-08-20

# DREILING OIL, INC.

Victoria, Kansas 67671

## K & G Oil Co. WELL LOG

Company	K & G Oil Co. Drawer 340 Plainville, KS 67663	Sec. 31	Twp. 8	Rng. 17
Farm	Dopita No. 3	Location	NE NW SW	
Total Depth	3,470'	County	Rooks	
Comm.	2-16-78 Comp. 2-22-78	Elevation:	2005	K. B.
Contractor	Dreiling Oil, Inc. Rt. #1 Victoria, KS 67671		2003	D. F.
			2000	G. R.

Casing Record  
 171' - 8 5/8"  
 3,469' - 5 1/2"

Cement Record  
 125 sacks cement  
 cemented w/175 sacks  
 common 10% Salt

Production:  
 K. B.  
 D. F.  
 G. R.

Figures Indicate Bottom of Formations

0'	176'	Shale
176'	418'	Shale
418'	1314'	Shale & Sand
1314'	1349'	Anhydrite
1349'	1680'	Shale
1680'	2420'	Lime & Shale
2420'	2550'	Lime
2550'	3009'	Shale & Lime
3009'	3470'	Lime
3470'	T.D.	

RECEIVED  
 KANSAS CORP COMM  
 1997 APR -1 A 11:46  
 4/1/97

STATE OF KANSAS)  
 )ss  
 COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Dopita #3.

  
 JOSEPH A. HESS

Subscribed and sworn to before me this 28th day of February, 1978

  
 Cecilia Basgall Notary Public

My appointment expires: November 17, 1980.

CECILIA BASGALL  
 NOTARY PUBLIC  
 Ellis County, Kansas

GEOLOGICAL REPORT

15-163-20773-00-00

K & G OIL COMPANY  
 Drawer 340  
 Plainville, Kansas  
 67663

Re: K & G Oil Company  
 #3 Dopita J  
 NE-NE-SW, Sec. 31-8s-17w  
 Rooks, County, Kansas

Dear Sir:

The following is the geological report for the above captioned well.

CONTRACTOR: Dreiling Oil, Inc.  
 COMMENCED: 2/16/1978  
 COMPLETED: 2/21/1978  
 ELEVATION: 2000' GL, 2003' DF, 2005' KB.  
 DRILL STEM TESTS: None  
 ELECTRIC LOG: Dresser Atlas 2800'-3470'  
 CASING RECORD:  
     SURFACE: 8 5/8" set @ 171'  
     PRODUCTION: 5 1/2" set @ appx. 3469'

4/1/77  
 RECEIVED  
 KANSAS CORP COMM  
 APR 11 1977  
 A.M. 11:16

FORMATION TOPS  
 (Keel Bushing Elevations)

FORMATION	DEPTH (SAMPLE)	DEPTH (LOG)	SUBSEA (LOG)
Anhydrite	1314-1349	1314-1348	+691 657
Topeka	2902	2904	-8 8
Queen Hill Sh.	3055	3054	-1 49
Heebner	3116	3116	-1 11
Toronto	3134	3138	-1 33
Lansing-K. C.	3155	3158	-1 53
Base K. C.	3380	3381	-1 76
Arbuckle	3416	3415	-1 10
R. T. D.	3470	3471	-1 56