

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-163-01383-00-00

API NUMBER N/A

LEASE NAME Ted Hrabe

WELL NUMBER 2

2310 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 36 TWP. 8s RGE. 17w(R) or (W)

COUNTY Rooks

Date Well Completed Sept. 1961

Plugging Commenced 12-20-96

Plugging Completed 12-20-96

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR S & M Oil

ADDRESS 2730 Thunderbird Drive

PHONE#(913) 628-3658 OPERATORS LICENSE NO. 8735

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 1996 (date)

by Deanna Hamel (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? N/A

Producing Formation Kansas City Depth to Top 3091 Bottom 3334 T.D. 3394 PBTD 2800'

Show depth and thickness of all water, oil and gas formations. Packerstuck/1850'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Anhydrite		1244	1280			
Kansas City		3091	3334	4 1/2	3394	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Ran measuring line and tubing to 1850' Perf. casing at 1260, 750, 200'

Spot cement at 1864' 85sk.circ cement; Pulled tubing and squeezed well with 15 additional sks at 300 psi. (60/40-10%/400#hulls & 1/4#flo-seal)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License RECEIVED

KANSAS CORPORATION COMMISSION

Address Russell, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: S & M Oil JAN 09 1997


STATE OF KANSAS COUNTY OF ELLIS, ss. 1/9/97

CONSERVATION DIVISION

S+M OIL (Employee of Operator Wichita KCC Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Crawford

(Address) 2730 Thunderbird DR. Hays, Ks.



SUBSCRIBED AND SWORN TO before me this 8 day of January, 19 97

Roberta Angell  
 Notary Public

My Commission Expires: 10-24-2000