

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-163-20798-00-00

API NUMBER 15-N/A

LEASE NAME Russ

WELL NUMBER 7

3630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 31 TWP. 8 RGE. 17 (E or W)

COUNTY Rooks

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-25-95

Plugging Completed 7-25-95

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR The Gene Brown Company

ADDRESS PO Box 220 Plainville, Ks. 67663

PHONE# ( ) 913-434-4811 OPERATORS LICENSE NO. 5635

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-18-95 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation LKC ARB Depth to Top 3000 Bottom 3357 T.D. 3399

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil & Water	3000	3294	8 5/8	151	None
ARB	Oil & Water	3352	3357	5 1/2	3399	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
50 sks com cement W/300# hulls Followed W/10 sks gel Followed W/175 sks cement

100# hulls 400# max press 200# shut in pressure Pump down annulus W/25 sks  
W/100# hulls 400 psi max press 200 psi shut in pressure  
Well was perforated 2 holes @ 2050' 1280' 725'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc License No. \_\_\_\_\_

Address PO Box 31 Russell, Ks 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Gene Brown Company

STATE OF Kansas COUNTY OF Rooks, ss. AUG 16 1995 8/16/95

Don Brown

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.


(Signature) Don Brown

(Address) P.O. Box 220 Plainville Ks 67663

SUBSCRIBED AND SWORN TO before me this 15<sup>th</sup> day of August, 19 95

Bonita K. Schubert  
 Notary Public.

My Commission Expires: July 2, 1997



RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 16 1995 8/16/95