

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-20,988 *0560*

LEASE NAME Russ A

WELL NUMBER 4

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 31 TWP. 8 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed --

Plugging Commenced 07-25-95

Plugging Completed 07-25-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR The Gene Brown Company

ADDRESS PO Box 220 Plainville, Ks 67663

PHONE# () 913-434-4811 OPERATORS LICENSE NO. 5635

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-18-95 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation LKC ARB Depth to Top 3132 Bottom 3424 T.D. 3466

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil & Water	3132	3358	8 5/8	160'	None
Arbuckle	Oil & Water	3421	3424	5 1/2	3443	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perforate 2 holes @ 2050' 1330' 750' Run tubing to 2100 ft Spot 150 sks cement
W.400# hulls Pull to 1050' Cement W/175 sks 350# hulls Pull tubing to 500'
Cement W/50 sks W.250# hulls Pull tubing fill hole W/25 sks cement Pump down
backside W/25 sks cement 100# hulls 150 PSI max and shut in 100 psi
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc License No.

Address PO Box 31 Russell, Ks

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Gene Brown Company

STATE OF Kansas COUNTY OF Rooks, ss.

Don Brown

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Don Brown

(Address) PO Box 220 Plainville Ks

SUBSCRIBED AND SWORN TO before me this 15th day of August, 19 95

Bonita K. Schubert
 Notary Public

My Commission Expires: July 2, 1997



RECEIVED
 STATE CORPORATION COMMISSION
 AUG 16 1995
 8/16/95
 WICHITA, KANSAS