

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-22734 0000

LEASE NAME Dopita A

WELL NUMBER 10

380 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 31 TWP. 8 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 9-29-85

Plugging Commenced 6-3-87

Plugging Completed 6-3-87

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Kenny Brown Enterprises

ADDRESS 400 N Washington Plainville, Kansas

PHONE#( 913 434-7236 ) OPERATORS LICENSE NO. 5537

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Hays, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3382' Bottom 3385' T.D. 3393'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface Casing			8 5/8"	217'	0
	Production Casing			5 1/2"	3405	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped into 5 1/2" casing 175 sack econ-o-litew/ 4 sacks hulls. Max PSI 1200#.

Shut in 1000# (One solid plug from top to bottom)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address Hays, Kansas 67601

STATE OF Kansas COUNTY OF Rooks, ss.

Kenneth O Brown (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Kenneth O Brown

(Address) 400 N Washington Plainville, Kansas

SUBSCRIBED AND SWORN TO before me this 8<sup>th</sup> day of September, 19 87

Barbara West Notary Public

My Commission Expires:



RECEIVED  
 STATE CORPORATION COMMISSION  
 67663  
 6/9/87  
 CONSERVATION DIVISION  
 Wichita, Kansas

# Kenny Brown Enterprises

DRAWER 340

PLAINVILLE, KANSAS 67663

Dopita A-10  
Gr. Elevation 1933  
KB 1938  
API # 15-163-22,7340000

9-9-85-Rigged up and drilled 219' of 12 $\frac{1}{4}$ " surface hole. Ran 217' of new 8 5/8"-20# casing. Cemented with 135 sacks of Halliburton quick set 3% C.C. Plug down @ 11:15 PM Cemented circulated.

9-10-85-Drilling @ 7:00 A.M.	304'	Anky	1234	+ 704
9-11-85-	"	"	1273	+ 665
9-12-85-	"	"	2828	- 890
9-13-85-	"	"	3045	- 1107
9-14-85-	"	"	3065	- 1127
		LKC	3087	- 1149
		Base	3316	- 1378
		Arbuckle	3355	- 1417
		TD	3410	- 1472

Reached TD A 3410, circulated 1  $\frac{1}{2}$  hrs, layed down drill pipe. Ran open hole log. Ran 83 jts. of 5  $\frac{1}{2}$ " casing 15 $\frac{1}{2}$ "#, 10' shoe jt., 1' guide shoe. Cemented w/ 325 sacks of Halliburton Econolete,,135 sacks EA-2. Plug down @ 5:15 P.M.

Ran 3 baskets @ top of arbuckle, top Topeka, Top of ankydrite. Ran 6 Centralizer on 1, 4, 7, 10, 13, 52-Anky, Plug @ 3397.

5/18/87

RECEIVED  
STATE CORPORATION COMMISSION

MAY 18 1987

CONSERVATION DIVISION  
Wichita Kansas