

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-30183-00-00

LEASE NAME Dopita A

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER # 5

1980 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Kenneth O Brown d/b/a Kenny Brown Enterprises

SEC. 31 TWP. 8s RGE. 17 (E) or (W)

ADDRESS Drawer 340 Plainville, Kansas 67663

COUNTY Rooks

PHONE# (913) 434-7236 OPERATORS LICENSE NO. 5537

Date Well Completed 6-74

Character of Well oil

Plugging Commenced 1-28-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-28-92

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Hays, Kansas (Dennis Hamel)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Kansas City Depth to Top 2900' Bottom 3350' T.D. 3351'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface Pipe			8 5/8"	171'	0
	Production Casing			5 1/2"	3424'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

300 sks 60/40 pos mix, 10% gel, 1/4# flocele, 500# Halls

Pumped 40 sks behind- 8 5/8"

" 260 sks- 5 1/2"-one solid plug.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services

License No. \_\_\_\_\_

Address 1102 E 8th. Hays, Kansas 67601

STATE OF Kansas

COUNTY OF Rooks, ss.

Viola E Brown

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Viola E Brown

(Address) Drawer 340 Plainville, Kansas 67663

SUBSCRIBED AND SWORN TO before me this 30<sup>th</sup> day of January, 19 92

Barbara West  
Notary Public

My Commission Expires: \_\_\_\_\_




2/3/91  
RECEIVED  
STATE CORPORATION COMMISSION  
FEB 03 1991  
CONSERVATION DIVISION  
WICHITA, KANSAS

WELL LOG 15-163-30183-00-00

COMPANY K & G Oil Company  
FARM DOPITA NO. "A" #5

SEC. 31 T. 8S R. 17W  
LOC. C N/2 NW SE

RIG. NO. 8  
TOTAL DEPTH 3425'  
COMM. 5-13-66 COMP. 5-20-66



SHOT OR TREATED  
CONTRACTOR ISSUED Murfin Drilling Company

CASING  
20 10  
15 8 5/8" - 171' w/130 sacks  
12 6  
13 5 1/2" - 3424' w/200 sacks

ELEVATION  
PRODUCTION oil

FIGURES INDICATE BOTTOM OF FORMATIONS

- 40 Post Rock
- 172 Shale
- 990 Shale & Sand
- 1285 Red Bed
- 1324 Anhydrite
- 1715 Shale & Shells
- 1820 Shale & Lime
- 2557 Lime & Shale
- 2910 Shale & Lime
- 2995 Lime & Shale
- 3396 Lime
- 3425 Arbuckle
- 3425 RTD

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
(DATE UNREADABLE)

State of KANSAS  
County of SEDGWICK } ss:

I, Maurice Langley, Jr. of the Murfin Drilling Company  
upon oath state that the above and foregoing is a true and correct copy of the log of the DOPITA "A" #5 well.

MURFIN DRILLING COMPANY  
By: Maurice Langley, Jr.

Subscribed and sworn to before me this 29th day of June 19 66

My Commission Expires: ADELA MIZENER, Notary Public  
My commission expires November 5, 1966

Adela Mizener  
NOTARY PUBLIC