

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R. 62-3-117

API NUMBER 15-163-21,950-00-00

LEASE NAME Eckart "B" OWWO

WELL NUMBER #1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 15 TWP. 8 RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 12/05/89

Plugging Commenced 12/26/02

Plugging Completed 12/30/02

RECEIVED  
01-08-2003  
JAN 08 2003

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th Street, Newton, KS 67114-8827

PHONE# (316) 799-1000 OPERATORS LICENSE NO. 30742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 26, 2002 (date)

by Richard Williams (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached?         

Producing Formation          Depth to Top 3351' Bottom 3351' T.D. 3380'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	241'	8-5/8"	241'	0'
	Production	0'	3379'	4-1/2"	3379'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Run tar block on tubing. Got to 480', hit bridge, another @ 660' & stopped @ 830'. Came out. Run tubing back in open-ended to 1410' - call for plugging orders. Spot 160sx cement. Pull to 700'. spot 60sx cement w/250# hulls. Pull to 300'. spot 65sx cement w/550# hulls. Circ. cement up 4-1/2" & 8-5/8". Pull tubing out. Tie onto 4-1/2" spot 10sx up 8-5/8" and 5sx down 4-1/2". Top well off. Shut in & left set overnight. Next morning, cement was 60' down in 4-1/2". Tore down & moved off.


Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

 KAREN J. MITCHELL  
Notary Public, State of Kansas  
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED AND SWORN TO before me this 7th day of January, 2003

Karen J. Mitchell  
Notary Public

My Commission Expires: April 13, 2006

OR