

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23,188 -00-00

LEASE NAME Rostocil

WELL NUMBER 1

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 17 TWP. 8S RGE. 18 NE1/4(W)

COUNTY Rooks

Date Well Completed 11/21/91

Plugging Commenced 11/21/91

Plugging Completed 11/21/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Edwin C. Schuett & Sharp Engineering

ADDRESS 1616 Glenarm Place, #1804

PHONE# (316) -733-1989 OPERATORS LICENSE NO. 30722

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-21-91 (date)

by Ed Shumaker (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	252'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mud laden fluid 3500'-3452' 40 sks cement @ 300'
20 sks cement @ 3452' 10 sks cement @ 40'
20 sks cement @ 1440' 15 sks in rathole
100 sks cement @ 820' 15 sks in mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, russell, KS 67665-0506


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Edwin C. Schuett & Sharp Engineering NOV 25 1991

STATE OF KANSAS COUNTY OF RUSSELL, ss. 11-25-91

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 506, Russell, KS 67665-0506



SUBSCRIBED AND SWORN TO before me this 22nd day of November, 19 91

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

My Commission Expires: 2-6-92

15-163-23188-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Edwin C. Schuett & Shharp Engineering
1616 Glenarm Place, #1804
Denver, Colorado 80202

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Rostocil

WELL #1

LOCATION: SW SW SE
Section 17-8S-18W
Rooks County, Kansas

LOGGERS TOTAL DEPTH: 3500'

ROTARY TOTAL DEPTH: 3500'

COMMENCED: 11/15/91

CASING: 8-5/8" @ 252' w/150 sks cement

ELEVATION: 2026' K.B.

COMPLETED: 11/21/91

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	90'	Shale	1443'
Dakota Sand	620'	Shale & Lime	2173'
Red Bed	858'	Shale	2689'
Cedar Hills	920'	Lime & Shale	3110'
Red Bed	1120'	Arbuckle	3452'
Anhydrite	1409'	R.T.D.	3500'

NOV 25 1991

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Kyle B. Branum

Kyle B. Branum

Subscribed and sworn to before me on November 22, 1991.

My commission expires: February 6, 1992.



Glenda R. Tiffin

Glenda R. Tiffin, Notary Public