

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1972
DEC 26 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas 67202

Lease Name Tanzey Well No. 1

Location C NW SW Sec. 25 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3424'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 2:15 P Day 21 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 3424' 12" csg set at 26' CWC ~~5 1/2" csg set at 1336' W/ exp. 6700 cmt 1972~~

5 1/2" csg set at 3415' cem W/ 100 sx.

Filled 5 1/2" csg W/sd (3400-3424) Dumped 5 sk cmt W/dump bailer. (336503400)

Shotoff 5 1/2" csg at 691'.

Pulled 5 1/2" csg to 600' -pumped 25 sk gel & water, displaced 70 sk cmt.

Pulled 5 1/2" csg to 200' -pumped 10 sk gel & water, circulated 150 sx cmt to base of cellar.

Pulled remaining 5 1/2" csg and capped hole.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. W. Massey
Well Plugging Supervisor

INVOICED

DATE 12/26/72

INV. NO. 6772-W