



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Co.

Complete Address 1130 Wichita Plaza, Wichita, Kansas

Lease Name Vallete Well No. 4

Location W/2 E/2 SE Sec. 25 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3439

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Rains & Williamson Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 1:15 P Day 18 Month 7 Year 1969

The above well was plugged as follows:

RTD 3439' 8 5/8 csg set at 208' cwc Cmt. <sup>ml</sup>at. 50-50 poz cmt. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar. Plugged rat hole with 2 sk cmt.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 22 1969 *JUL 22, 1969*

I hereby certify that CONSERVATION DIVISION  
Wichita, Kansas plugged as herein stated.

INVOICED

DATE 7/23/69  
INV. NO. 132-W

Signed: *Leo J. Massey*  
Well Plugging Supervisor