

*SP*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

AUG 2 1972  
AUG 2 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Hershberger Explorations, Inc.

Complete Address Suite 230 O. W. Garvey Bldg., Wichita, Kansas

Lease Name Bird Well No. 1

Location C E/2 SW SW Sec.      Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3461'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor H-30 Drlg.

Address Wichita, Kansas License No.     

Operation Completed: Hour 2 P Day 1 Month 8 Year 1972

The above well was plugged as follows:

RTD 3461' 8 5/8 csg set at 205' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED  
DATE 8/3/72  
INV. NO. 6114-W