

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 5 1966

DEC 5, 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 553 Russell, Kansas

Lease Name McMillen "B" Well No. 5

Location C SE SW NE Sec. 25 Twp. 8 Rge. 18 (E) (W) X

County Rooks Total Depth 3460'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Peel Bros.

Address: Hosington, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 9:30 A Day 30 Month 11 Year 1966

The Above well was plugged as follows:

RTD 3460' 8 5/8 csg set at 245' cwc.  
Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc  
cement thru drill pipe. Heavy mud to 230' set cementing plug and displaced 20 sc cem.  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement  
to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey  
Well Plugging Supervisor

DATE 12/6/66  
INV. NO. 4403-W