

R

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-02655-00-00

7/15/63

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bennett & Roberts Oil Operations
Complete Address: Drawer 633 Russell, Kans
Lease Name Hindman Well No. 2
Location SE NE SW Sec. 35 Twp. 8 Rge. (E) (W) 17
County Rooks Total Depth 3390
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Glenn & Smith
Address: Ellinwood, Kans License No. 396
Operation Completed: Hour 12:30PM Day 11 Month 7 Year 63

The Above well was plugged as follows:

8 5/8" 237' circulated with cement - 5 1/2" 3389' with 200 sax cement -
Perf 3083'
PB with sand to 3060', set 4 sax cement with dump bailer - pulled
2556' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550'
displaced 20 sax cement through 5 1/2" at 550', heavy gel mud to 180',
displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', cement
35' to bottom cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leon Letty
Well Plugging Supervisor

DATE 7-15-63
INV. NO. 7407-W