

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-163-21,586-00-00 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Hupher-Knord Oil Co.

Complete Address 2309 Walnut - Hays, Ks. 67601

Lease Name Shave "B" Well No. 1

Location NE-SW-SE Sec. 35 Twp. 8 Rge. 17 (East)(West)

County Roos Total Depth 3380 ^{109.85'}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie, Del.

Address 801 Union Ctr. - Wichita, Ks 67202 License No. _____

Operation Completed: Hour: 12:00 PM Day: 2 Month: 3 Year: 1982

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows:

8 5/8" set @ (245') w/190 In common - cmt line - 2% gel 3% CA-Cl (Sun) Spotted 70 sk @ 750' - Spotted 40 sk @ 240' - Spotted on solid bridge 10 sk @ 40' to 0' - Spotted 10 sk in rat hole - circulated heavy mud between plugs. Used 130 sk 50/50 foamix 4% gel. 3% CA-Cl + 8 5/8 plug. Cmt by Sun.

Amount of Surface Casing: 245'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 3-24-82
INV. NO. 9699-W

3/17/82