

DISTRICT CONSERVATION AGENT'S REPORT

15-163-00975-00-00

*Handwritten mark resembling a stylized '8' or '9' with a diagonal slash.*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 97-15  
LOCATION SW NW SW  
SEC. 26 TWP. 8 RGE. 18

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Radke

Operator El Dorado Refg Co Address Box 209 Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3490 Feet.

Plugging Contractor C. E. Shull

Plugging Contractor's License No. 8

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

3 5/8" at 215' circulated with cement - 5 1/2" at 3490' with

75 sax cement behind - perforated at 3460'.

Sand to 3450', set 4 sax cement with dump bailer, pulled

2400' 5 1/2" - heavy mud to 210', set rock and 15 sax cement,

mud to 55', set rock and 10 sax cement to bottom cellar.

*9-27-56*

*E. J. Lester*  
District Conservation Agent

Date 9-22-56

**PLUGGING**  
FILE SEC. 26 T. 8 R. 18 W.  
BOOK PAGE 97 LINE 15