

15-163-014 22-00 20

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

APR 19 1961
CONSERVATION DIVISION
Wichita, Kansas

4/19/61

File No. _____ County: _____ Rooks

Location: SW SE NE Sec. 33 Twp. 8 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3426

I have this date completed supervision of plugging of:

Lease Name: Lowry Well No. 4

Operator's Full Name: Natural Gas & Oil

Complete Address: Box 105 Great Bend, Kansas

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 9AM Day 15 Month 4 Year 61

The above well was plugged as follows:

8 5/8" 167' circulated with cement - 5 1/2" 3424' with 150 sax cement behind and squeezed at 1044' with 115 sax cement - PB to 3226' - perforated 3197' Filled with sand to 3160', set 5 sax cement with dump bailer, pulled 785' 8 5/8" - mudded hole to 450', set 15 sax cement at 450', heavy mud to 150', set 15 sax cement, heavy mud to 30', set 10 sax cement to bottom cellar.

Mudding and cementing by Knight Casing pulling

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 4/26/61

INV. NO. 2968-W