

15-163 02997-00-20

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW SE NE

SEC. 33 TWP. 8 RGE. 19W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Lowry

TRANS-ERA PET.  
Operator B & R DRG CO INC. Address Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3445 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 180' circulated with cement-5 1/2" at 3442 with  
100 sax cement behind.

Filled with caht ti 2700', set 4 sax cement with dump bailer,  
pulled 2100' 5 1/2", filled with mud to 180', set rock and 15  
sax cement, mud to 35', set rock and 10 sax cement to  
bottom cellar.

**PLUGGING**  
FILE NO. 33-8-R-1924  
BOOK PAGE 65 LINE 26

OCT 27 1952  
10/29/52  
*Edwin J. [Signature]*  
District Conservation Agent

Date 10-27-52