

15-We3-20595-00-00

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

JAN 16 1976

1/16/76

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Icer Addis

Complete Address Drawer 8038, Wichita, Kansas

Lease Name Cerrow Well No. 1

Location SW SW SW Sec. 33 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3485'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor H-30 Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 8:30 P Day 14 Month 1 Year 1976

The above well was plugged as follows:

RTD 3485' 8 5/8 csg set 190' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 650' thru drill pipe.

Heavy mud to 190' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

      

      

      

      

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Murray  
Well Plugging Supervisor

INVOICED

DATE 1-16-76

INV. NO. 2581-W