

15-163-04158-02-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 114-28

LOCATION NE SE SW

SEC. 33 TWP. 8 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 0 Lease Rostocil

Operator Skelley Oil Co Address Box 391 Hutchinson, Kans

Field _____ County Rooks

Total Depth 3450 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address _____

(Describe Briefly the manner in which the well was plugged)

13" at 197' circulated with cement - 8 5/8" at 1427' with

600 sax cement behind - 5 1/2" at 3446'

P.B. to 3193' perforated at 3186'.

Filled with sand to 3170', set 4 sax cement with dump bailer,

pulled 2000' 5 1/2" - , added hole to 600', set rock and 15 sax

cement - heavy mud to 48', set rock and 15 sax cemenet to bottom

cellar.

District Conservation Agent

11-10-56

Date _____

PLUGGING
FILE SEC 33 T 8 R 19 W
BOOK PAGE 114 LINE 28

11/16/56