

15-163-01424-0000

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE SW NW

SEC. 34 TWP. 8 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Verweke

Operator Petroleum Inc Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3401 Feet.

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR - 2 1951  
CONSERVATION DIVISION  
Wichita, Kansas  
3/2/51

(Describe briefly the manner in which the well was plugged)

8 5/8" at 239' circulated with cement - 5 1/2" at 3392' with  
35 sax cement behind.

Filled with sand to 3380', set 4 sax cement with dump bailer,  
pulled 5 1/2", pumped hole full mud, 20 sax Aquagel and 20 Sax  
Baroid, mixed with hulls, pumped cementing plug to 300', followed  
by 100 sax cement, filling hole from 300' to bottom cellar with  
solid cement.

Mudding and cementing by Globe Cementing Co.

**PLUGGING**  
FILE SEC 34 8 R 19  
BOOK PAGE 14 LINE 44

*[Signature]*  
District Conservation Agent

Date 2-27-51