



15-163-20316-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas

7/20/70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of Dreiling Drlg. has this

date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Landes Exp.

Complete Address: 418 Union Center

Lease Name: Verveka Well No. 1

Location: NW SW NW Sec. 26 Twp. 8 Rge. (E)(W) 19

County: Rooks Total Depth 3175 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Draper was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace  
70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent