



15-163-20748-00-00 FORM CP-2

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 10 1977  
CONSERVATION DIVISION  
Wichita, Kansas  
11/10/77

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of Dreiling Oil has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: J. B. Collins

Complete Address: 1007 Cody-Suite "A", Hays, Ks.

Lease Name: Veverka Well No. 5

Location: C N/2 S/2 NW/4 Sec. 26 Twp. 8 Rge. (E)(W) 19

County: Rooks Total Depth 3450' Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Draper was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set 70 sk cmt plug at 600' thru drill  
pipe. Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy  
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent