

State of Kansas



15-163-20220-50-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1969
CONSERVATION DIVISION
Wichita, Kansas
6/30/69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herman Johnson of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: I. O. Miller,

Complete Address: 619 Brown Building, Wichita, Kansas.

Lease Name: Grace Lowry Well No. 1

Location: NW-SW-SW Sec. 31 Twp. 8 Rge. (E)(W) 19

County: Rooks Total Depth 3603' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Johnson was instructed to plug the well as follows:

200' - 8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 565'.

Circulate hole with heavy mud. Pull DP to 750' and displace 100 Sx.
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

R. L. Nichols

Conservation Division Agent