

10-24

4-070075

HSE 8/26/05  
20,481-00-02

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-20,536

SW SE SW /4 SEC. 34, 08 S, 18 W  
330 feet from S section line  
3630 feet from E section line

Operator license# 9090

Lease: Peace "OWWO" Well # 1

Operator: Charter Energy, Inc.

County: Rooks 111.59

Address: P.O. Box 252  
Great Bend, Kansas 67530

Well total depth 3433 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 206 feet  
W/150 sxs.

ABAND. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD. \_\_\_\_\_, D&A \_\_\_\_\_

Plugging contractor: Charter Energy, Inc. License# 9090

Address: P.O. Box 252 - Great Bend, Kansas 67530

Company to plug at: Hour: 9:30 A.M. Day: 24 Month: October Year: 1997

Plugging proposal received from: Steve Baize

Company: Charter Energy, Inc. Phone: 316-792-4745

Were: 8 5/8" 206' w/150 sxs. 4 1/2" 3398' w/ NA sxs. PBD 3354'.  
Squeeze at 2168' - 2230' w/150 sxs. Squeeze at 1000' w/250 sxs.  
Squeezed at 731' - 761' w/100 sxs.  
Dakota 483' - 758'. Anhy. 1387' - 1425'. Salt 1732' - 1817'.  
Fluid level 900' - Dakota break.  
Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

1997 OCT 29  
68100 Tbb1

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part [ ], None [ ]

Completed: Hour: 2:00 P.M., Day: 24, Month: October, Year: 1997

Actual plugging report: Ran tubing to 2000'. Allied pumped 115 sxs 60/40 pozmix - 10% gel w/400# hulls. Cement circulated. PTOH. Squeezed 50 sxs. Max. P.S.I. 500#. S.I.P. 250#. Pumped 5 sxs. Max. P.S.I. 800#. S.I.P. 500#.

Remarks: Emergency plug orders while rig over hole.

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD  Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_ Elevation: 1983 GL

I did  / did not [ ] observe the plugging.

Richard Williams  
(agent)

Form CP-2/3

INVOICED

DATE OCT 30 1997  
INV. NO. 49400