

4-041577

5-5

00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,440

SE NE NW /4 SEC. 36, 08S, 19 W
4290 feet from S section line
2970 feet from E section line

Operator license# 5635

Lease Weigel well # 3

Operator: Gene Brown Company

County Rooks

Address: Drawer 220
Plainville, Kansas 67663

Well total depth 3429 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 156 feet
w/90 sxs.

111.44

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 5 Month: May Year: 94

Plugging proposal received from: Tom Brown

Company: Gene Brown Company Phone:

Were: 4 1/2" casing set @ 3424' w/160 sxs. cement. Perf. @ 3328' -
3207'. Salt @ 2020' - Any. @ 1350' - Dakota @ 775' - W.L.M. 3300' -
T.O.F. @ 1200'.

Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:30P.M., Day: 5, Month: May, Year: 94

Actual plugging report: R.I.H with perforatin to perf casing @ 2020' -
1350' - 775'. Rig up cementer - pumped in 4 1/2" casing 225 sxs.
cement with 400# hulls. Max. 300#. Hooked-up to 8 5/8" S.P. Pumped in
50 sxs. cement with 100# hulls. Max. 300#.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did observe the plugging.

Dennis L. Hamel

INVOICED

DATE 5-18-94

INV. NO. 40445

5-5

(agent)

Form CP-2/3

RECEIVED STATE CORPORATION COM

MAY 16 1994

CONSERVATION DIVISIO
Wichita, Kansas

S-16-94