

4-042029

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-01,039-0000

C NE SE /4 SEC. 14, 08 S, 19 W
1980 feet from S section line
660 feet from E Section line

Operator license# 32287
Operator: Lost Creek Oil
Address: 1225 14 Road
Stockton, Kansas 67669

11/15

Lease: Hance "B" Well # 1
County: Rooks 114.40

Well total depth 3520 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 220 Feet
W/cwc sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 1:00 P.M. Day: 15 Month: November Year 1999

Plugging proposal received from: Carl Hance

Company: Lost Creek Oil Phone: -

Were: Ordered 250 sxs 60/40 pozmix - 10% gel plus 600# hulls.
4 1/2" casing set at 3520' w/150 sxs cement. Perfs at 2936' - 3442'.
Perf anhy at 1460' - Dakota at 850' - T.O.F. at 2000'.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 5:00 P.M. Day: 15, Month: November, Year: 1999

Actual plugging report: R.U. Cementers to 8 5/8" S.P. Squeezed annulus with 50 sxs cement with 100# hulls mixed in cement. Max. P.S.I. 800#. R.U. Cementers to 4 1/2" casing - squeezed 200 sxs cement with 500# hulls mixed in cement. Max. P.S.I. 600#. S.I.P. 100#.

Remarks:
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC X, NO
Plugged through TUBING CASING X. Elevation: G.L.

I did [X] / did not [] observe the plugging.

INVOICED
DATE 12/6/99
WV. NO. 60919

100

Dennis L. Hamel
STATE CORPORATION COMMISSION
Form CP-2/3

11-29-99 NOV 29 1999
CONSERVATION DIVISION
Wichita, Kansas