

4-041619

8-31

987-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,989

NE NE /4 SEC. 34, 08 S, 18 W
3630 feet from S section line
990 feet from E section line

Operator license# 5635

Lease Harris well # 4

Operator: Gene Brown Company

County Rooks

Address: P.O. Drawer 220
Plainville, Kansas 67663

Well total depth 3525 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet

114.56

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 31 Month: August Year: 94

Plugging proposal received from: Tom Brown

Company: Gene Brown Company Phone:

Were: 4 1/2" casing set @ 3524' w/N/A sxs.cmt. Perf. @ 3130' - 3500'.
Salt @ 2000' - Anhy. @ 1480' - Dakota @ 800' - T.O.F. tubing @ 2600'.
Ordered 225 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00P.M., Day: 31, Month: August, Year: 94

Actual plugging report: Run in hole with tubing to 2600'. Spotted
100 sxs. cement with 200# hulls to circulate cement to surface.
Pulled tubing and squeezed casing with 25 sxs. additional cement.
Max 500# P.S.I. 8 5/8" S.P. Pumped 50 sxs. cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 150#.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation:

I did observe the plugging.

INVOICED

DATE 9-30-94

INV. NO. 41307

Dennis L. Hamel

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1994
Sep 30 1994
CONSERVATION DIVISION
WICHITA, KANSAS