

9-29-94

4-041665

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-21,189-00-00

NW NW NW /4 SEC. 34, 08 S, 18 W  
4950 feet from S section line  
4950 feet from E section line

Operator license# 5635 Lease Harris well # 5

Operator: The Gene Brown Company County Rooks

Address: P.O. Drawer 220 Well total depth 3410 feet <sup>110' 83</sup>  
Plainville, Kansas 67663 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 169 feet  
w/100 sxs.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# \_\_\_\_\_

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 29 Month: September Year: 94

Plugging proposal received from: Tom Brown

Company: The Gene Brown Company Phone: \_\_\_\_\_

Were: 4 1/2" casing set @ 3424' w/160 sxs. cement. Perf. @ 3356' -  
3110'. Perfs. salt @ 2000' - Anhy. @ 1350' - Dakota @ 750' - W.L.M.  
3300' - T.O.F. @ 2000'. Ordered 300 sxs. 60/40 pozmix - 10% gel with  
1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:15A.M., Day: 29, Month: September, Year: 94

Actual plugging report: Perf. casing at 750' - 1350' - 2000'. Hooked-up  
to 4 1/2" casing. Squeezed 220 sxs. 60/40 pozmix - 10% gel with 400#  
hulls down casing. Max. P.S.I. 400#. S.I.P. 100#.  
Hooked-up to 8 5/8" S.P. Pumped down 30 sxs. 60/40 pozmix - 10% gel  
with 100# hulls. Max. P.S.I. 300#.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES \_\_\_\_\_, CALC , NO \_\_\_\_\_ Dakota plug: YES , NO   
Plugged through TUBING \_\_\_\_\_, CASING . Elevation: \_\_\_\_\_ GL

I did  did not observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

MAR 31 1995  
MAR 31, 1995  
HAYS, KS

DATE 4-7-95  
INV. NO. 42511