

4-041579

5-5

00-00
18W

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,150

NE NE NW /4 SEC. 36, 08S, 16 W
4950 feet from S section line
2970 feet from E section line

Operator license# 5635 Lease Weigel well # 1

Operator: Gene Brown Company County Rooks

Address: Drawer 220 Well total depth 3494 feet 113.55
Plainville, Kansas 67663 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 168 feet
w/100 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 5 Month: May Year: 94

Plugging proposal received from: Tom Brown

Company: Gene Brown Company Phone:

Were: 4 1/2" casing set @ 3494' w/125 sxs. cement. Perf. @ 3450' -
3082'. Salt @ N/A - Anhy. @ 1300' - Dakota @ 775'.
Out of hole with tubing at 1300' - casing squeeze at 1000' with 300 sxs.
Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls,
plus ordered 100 sxs. common with 1/4# F.C.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00A.M., Day: 5, Month: May, Year: 94

Actual plugging report: 5-4-94 - Run in hole with 1300' tubing - spot
250 gal acid. 5-5-94 - Run tubing to 1300' - spot 100 sxs. common followed
with 20 sxs 60/40 pozmix - 10% gel - cement circulated at surface.
Pulled tubing. Hooked-up to 4 1/2" casing - squeezed 125 sxs. cement.
Max. 500#. Hooked-up to 8 5/8" S.P. Pumped in 50 sxs. cement with 100#
hulls. Max. 200#. Tubing stuck in the hole after circulation. Backed
off and pulled - 420'.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did X did not observe the plugging. Dennis L. Hamel

DATE 5-18-94
INV. NO. 40443
5-5

100

(agent)
Form CP-2/3

RECEIVED
STATE CORPORATION COM
MAY 16 1994
CONSERVATION DIVISION
Wichita, Kansas
5-16-94