

6 070528

NOV 20 1986

API NUMBER 15-163-00401-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW-NE-NW SEC. 22, T 8 S, R 19

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Operator: Kaiser-Francis Oil Co.

Name & Address P.O. Box 21468

Tulsa, OK. 74121-1468

Glen Jackson

_____ feet from S section line

_____ feet from E section line

Lease Name Peterson Well # J-2

County Nowata 111.41

Well Total Depth 3428 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8" feet 180

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. Titan License Number _____

Address Box 69 Hays, Kans. 67601

Company to plug at: Hour: 12:00 PM Day: 20th Month: Nov. Year: 19 86

Plugging proposal received from John Glenn & Glenn Jackson

(company name) Kaiser Francis Oil Co. (phone) 316-564-3214

were: 8 5/8" 180' S.P. cwc #100, 4 1/2" cog set @ 3412' w/d.k., 5 1/2" cog 2688-3428 Perforated

open hole 3428-3440, Proposal 250 5% 65/35 Formix Gel - 2% Additive, 6 3/4" 5% shells.

no pipe recovery, Perforate hydrocut @ 1475 and 870'

Load and pressure w/cement 8 1/2" + 4 1/2" annulus, Load and pressure 4 1/2" cog

with cement, Pump in with pump truck shut in under pressure

Plugging Proposal Received by Marion Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 Noon Day: 20th Month: Nov. Year: 19 86

ACTUAL PLUGGING REPORT Ordered 250 5% 65/35 Formix Gel - 2% Additive

and 6 3/4" shells, 2 5% Cello Flake.

Pumped in 4 1/2" cog 10 5% emt 1/4 5% cello flake, 3 5% shells,

and 115 5% cement 1/1 5% cello cement circulated out of annulus,

Pumped in another 125 5% emt, max. pressure 900 Psi.g.

shut in @ 400 Psi.g., Cemented by B.J. Titan.

Remarks: 4 1/2" cog was perforated @ 1475 & 870'

additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 12-9-86

Signed Marion Schmidt (TECHNICIAN)

INV. NO. 15522

11-20 JAN 08 1987