

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23361-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 22-8S-19W  
1020 feet from N Section Line, 900 feet from W Section Line  
Lease/Unit Name: JOHNSON Well Number: 2  
County: ROOKS Total Vertical Depth: 3449 feet

Operator License No.: 3077  
Op Name: JOHNSON OIL  
Address: 258 HWY 36  
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet: \$112.09  
Surface Casing: Size 8.625 feet: 229 w/150 sxs cmt  
Production: Size 5.5 feet: 3440 w/310 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/30/2002 11:00 AM

Plug Co. License No.: 3077 Plug Co. Name: JOHNSON OIL

Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL Phone: (785) 543-6171

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls - 13 sxs gel.  
D.V. Tool at 1453' cwc. PBTD 3380'.  
Fluid Level 1500'.  
LKC Perfs 3087' -3090'; 3180'-3183'; 3205'-3208'.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/30/2002 12:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 40 sxs 60/40 pozmix - 10% gel with 250# hulls,  
followed with 13 sxs gel spacer with 250# hulls, followed with 130 sxs 60/40 pozmix - 10% gel.  
Max. P.S.I. 1000#. S.I.P. 1000#.  
Hooked up to backside - instant pressure 500#.  
Note: D.V. Tool at 1453' cwc.

RECEIVED  
JAN 05 2003  
KCC WICHITA

1/6/03

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

10

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

1-7-03

NO. FOR

2003061042

Form CP-2/3

JAN 02 2003