

4-031671

3-8

12
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-23,196-00-00

SE SW SE /4 SEC. 25, 08 S, 19 W
330 feet from S section line
1650 feet from E section line

Operator license# 09860

Lease Slansky well # 1

Operator: Castle Resources, Inc.

County Rooks

Address: 1200 E. 27th Street
Bank IV - Suite C
Hays, Kansas 67601

Well total depth 3500 feet ^{113.75}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 241 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 08241

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 8 Month: March Year: 92

Plugging proposal received from: Larry

Company: Emphasis Oil Operations

Phone:

Were: Order 190 sx. 60/40 pozmix - 6% gel. - 3% c.c. - 8 5/8" W.P.
B.J. Services. Condition hole with heavy mud.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 6:00P.M., Day: 8, Month: March, Year: 92

Actual plugging report:

Spot plugs with drill pipe with 25 sx. @ 1450'.
8 5/8" set @ 241' w/140 sx. 100 sx. @ 850' w/hulls.
40 sx. @ 300'.
10 sx. @ 40' W.P.

Circulate 15 sxs. in Rathole.
Elev. 2026' GL. - Anhy. 1444' - 81'.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2026 GL

I did / did not X observe the plugging.

Carl Goodrow

DATE 4-14-92
INV. NO. 34948

3-10-92

100

(agent)