

6 070529

NOV 20 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-00080-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568
Operator: Kaiser-Francis Oil Co.
Name & Address P.O. Box 21468
Tulsa, OK. 74121-1468
Glenn Jackson

_____ feet from S section line
_____ feet from E section line

Lease Name Veverka Well # 1
County Rocko. 112.16
Well Total Depth 3451 feet
Conductor Pipe: Size 13" feet 148'
Surface Casing: Size 8 5/8" feet 143'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. Titan License Number _____

Address Box 69 Hays, Kans. 67601

Company to plug at: Hour: 2:13 PM Day: 20th Month: Nov. Year: 19 86

Plugging proposal received from John Glenn + Glenn Jackson

(company name) Kaiser-Francis Oil Co. (phone) 316-564-2214

were: 13" conductor @ 118' CUC / N.A., 8 5/8" SP 143' CUC / N.A., 4 1/2" cog
Sit @ 3444' 100' SK cont, open hole to Pipe Recovery.

Proposal - Order 250 100' SK 65' 10% 2% Additive, 2 SK Cello Slake and 6 SK
with pump truck load and Squeeze 4 1/2" and 8 5/8" annulus w/ cement.
also load and Squeeze 4 1/2" cog w/ cement. (Refer to log @ 1475'
and Dakota @ 870 ft. Plugging Proposal Received by Marion J. Schmitt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:13 PM Day: 20th Month: Nov. Year: 19 86

ACTUAL PLUGGING REPORT Ordered 250 100' SK 65' 10% 2% Additive
2 SK Cello Slake and 6 SK Shells, Pumped in with pump truck
Pumped in 4 1/2" + 8 5/8" annulus w/ 150' SK cont w/ 3 SK Shells, 50 PSI.9
Pumped in 4 1/2" cog, 10 SK cont w/ 2 SK Cello Slake, 3 SK Shells, and 90 SK cont.
may pressure 900 PSI.9, shut in @ 700 PSI.9
Cemented by B.J. Titan, Hays, Mo

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-9-86

INV. NO. 15521

Signed Marion J. Schmitt
(TECHNICIAN)

JAN 08 1987