

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19021-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 21-8S-19W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: STICE Well Number: 2
County: ROOKS Total Vertical Depth: 1231 feet

Operator License No.: 5386
Op Name: PRODUCTION DRILLING, INC.
Address: PO BOX 680
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1476
Production: Size 5.5 feet: 1231 212 SX CMT
Liner: Size feet:

Well Type: SWD UIC Docket No: D21220.0 Date/Time to Plug: 04/02/2002 7:30 AM
Plug Co. License No.: 5386 Plug Co. Name: PRODUCTION DRILLING, INC.
Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1118

Proposed Plugging Method: Ordered out 150 sxs Swift Multi-Density Cement with 600# hulls.
5 1/2" casing cwc.
Perfs 1100' - 1150' Cedar Hills.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/02/2002 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 110 sxs Swift Multi-Density Cement with 600# hulls.
Max. P.S.I. 300#. S.I.P. 300#.
Hooked up to backside instant 500#.
(Cement cwc on 5 1/2" casing).
Note: Lease originally known as Silvers #1. Paperwork referred to as Stice #1 SWD-OWWO. Docketed as Stice #2.

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 4-10-02

INV. NO. 2002061635

APR 04 2002

21-8-19W
NW NW NE

GEOL _____ FIELD _____
IN 2025 CW E 11/5/80 CARD ISSUED 2/26/81 IF SWDW
CED HILL 1100-50

NOT ASSIGNED

[illegible]

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

OLD INFO: OPERATOR WAS AYLWARD
PRODUCTION CO., #1 SILVERS, SPD 2/
15/47, SET 8" 1485 & 5" 3466, COMP-
LETED AS 24 BOPD 4/11/47

BAIL 1/2 BOPH/2 HRS: A/500 SWB 8 BOPH
DEC TO 3 BOPH: A/2000
PMP 12 BOPH: LWP 3450 PERF 36/3215-51
12/3220-24 A/1000
285' WTR & 180' OIL/12 HRS SWB 12
BOPH/12 HRS SO 3465-69, SO 3468-72

NEW INFO: RE-ENTERED EST 11/5/80,
SET 5" 1227, MLOT - CO, PF (CED HILL)
1100-50, SWDW - INJECTION RATE
SATISFACTORY