

4-070109

8-25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-20,322 00-00

SW SE NW /4 SEC. 21, 08 S, 19 W  
2970 feet from S section line  
3630 feet from E section line

Operator license# 5386

Lease: Stice Well # 1

Operator: Production Drilling, Inc.

County: Rooks 113.92

Address: 1023 Reservation Road  
Hays, Kansas 67601

Well total depth 3505 feet  
Conductor Pipe: 0 inch @ 0 sxs.  
Surface pipe 8 5/8 Inch @ 249 feet  
W/150 sxs.

ABAND. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD. \_\_\_\_\_, D&A \_\_\_\_\_

Plugging contractor: Production Drilling, Inc. License# 5386

Address: 1023 Reservation Road - Hays, Kansas 67601

Company to plug at: Hour: 5:00 P.M. Day: 25 Month: August Year: 1998

Plugging proposal received from: Gaylord Burroughs

Company: Production Drilling, Inc. Phone: 785-625-1189

Were: 4 1/2" set at 3504' w/100 sxs.  
D.V. Tool at 1500' w/250 sxs.  
Perfs. 3170' - 3410'.  
Ordered 185 sxs of Mid Con II with 500# hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All  , Part  , None

Completed: Hour: 6:00 P.M. Day: 25 , Month: August , Year: 1998

Actual plugging report: Halliburton pumped 30 bbls or 50 sxs of Mid Con II, followed with 30 bbls or 50 sxs of Mid Con II with 400# hulls, followed with 43 bbls or 77 sxs of Mid Con II. Max. P.S.I. 400#. S.I.P. 250#. Hooked on backside. Pressured up to 850#. Released pressure.

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31, 1998  
AUG 31 1998

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES  , CALC \_\_\_\_\_ , NO \_\_\_\_\_ Dakota plug: YES  , NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_ , CASING  . Elevation: 2047 GL

I did  / did not  observe the plugging.

Richard Williams  
(agent)  
Form CP-2/3

INVOICED

DATE SEP 01 1998

INV. NO. 51237

8-25 JAN 29 1999

(4)