

8

9-20

6 020521

API NUMBER 15-163-01398-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C SW SW SW, SEC. 22, T 8 S, R 19 W7EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Green B Well # 1

Operator: Kaiser Francis Oil Co.  
Name & Address 6733 S Yale

County Rooks 110.99

Box 21468

Well Total Depth 3415 feet

Tulsa, Ok. 74121

Conductor Pipe: Size \_\_\_\_\_ feet

918-494-0000

Surface Casing: Size 8 5/8 feet 155 w/127 sks

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kaiser Francis License Number 6568

Address Same as above

Company to plug at: Hour: 9:30 Day: 20 Month: Sept Year: 19 89

Plugging proposal received from John Glenn

(company name) Kaiser Francis (phone) \_\_\_\_\_

were: Order 250 sks 65/35 poz 6% gel 5 sks hulls. Spot with drill pipe with no

less than 36 vis mud between all plugs with good circulation and no fluid loss.

5 1/2" 3413' w/75 sks. Perf 3002 - 3247.

Squeeze 274 w/250' sks and at 1090 w/150 sks.

Shot three holes at 1475.

Plugging Proposal Received by Gil Balthazor  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00AM Day: 20 Month: Sept Year: 19 89

ACTUAL PLUGGING REPORT Pumped down 5 1/2" casing.

Cement in annulus at top.

1st plug 50' sks 65/35 poz 6% gel

2nd plug 200' sks w/mix w/500 lbs hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 14 1989  
CONSERVATION DIVISION

Remarks: B. J. Titan

(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE NOV 16 1989  
INV. NO. 26475

Signed Gilbert Balthazor  
(TECHNICIAN)  
Gilbert Balthazor