

6 070530

NOV 20 1986

API NUMBER 15-163-01400-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW-SW-NW SEC. 22, T 8 S, R 19

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568
Operator: Kaiser-Francis Oil Co.
Name & Address: P.O. Box 21468
Tulsa, OK. 74121-1468
Glenn Jackson

_____ feet from S section line
_____ feet from E section line

Lease Name Peterson Well # 1
County Rooks 112.39
Well Total Depth 3458 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 10 3/4 feet 185'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.V. Titan License Number _____

Address Box 69 Hays, Kans. 67601

Company to plug at: Hour: 3:30 PM Day: 20th Month: Nov. Year: 19 86

Plugging proposal received from John Klemm - & Glenn Jackson

(company name) Kaiser-Francis Oil Co (phone 916-564-3214)

were: 10 3/4" 185' cml #150 SK, 7" csg set @ 3450' #150 cmt SK, 5 1/2" lined to 3449' #N.A., open hole, No pipe recovery, Sakote Cement / U.K.
Proposal - Order 275 SK 65 / 125 Formix Gel - 2% Additive - 2 SK cello Slake, and 6 SK shells, With pump truck load and pressure 10' + 7" annulus, 7" csg and 5 1/2" csg annulus with cement, and then load + pressure 5 1/2" csg with cement.

Plugging Proposal Received by Marion Schmidt (TECHNICIAN)
Perforate Annulus @ 1475' and 870'

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 PM Day: 20th Month: Nov. Year: 19 86

ACTUAL PLUGGING REPORT 10 3/4" Cml @ 185' cml #150 cmt SK, 7" csg set @ 3450' #150 cmt SK
5 1/2" csg set @ 3449' #N.A., open hole 7 ft. No pipe recovery. Perforated at 1475' and 870', ordered 275 SK 65 / 125 Formix Gel - Additive, 2 SK cello Slake + 6 SK shells with pump truck pumped in 10' + 7" annulus 125 cmt #1/2" shells, 200 Psi.g. Pumped in 7' + 5 1/2" annulus - No Cement, 1000 Psi.g. Pumped in 5 1/2" csg #150 cmt #1/2" cello + #1/2" shells (Mag 600 - 51.300)

Remarks: Cemented by B.V. Titan, Hays
11-25-86 (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-9-86

INV. NO. 15520

JAN 08 1987

Signed Marion Schmidt (TECHNICIAN)