

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01400-00-01  
Spot: NWSWNW Sec/Twnshp/Rge: 22-8S-19W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: PETERSON OWWO Well Number: 1  
County: ROOKS Total Vertical Depth: 3458 feet

Operator License No.: 3077  
Op Name: JOHNSON OIL  
Address: 258 HWY 36  
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet: \$112.39  
Surface Casing: Size 10.75 feet: 187  
Production: Size 7 feet: 3449  
Liner: Size 5.5 feet: 1467

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/30/2002 12:30 PM  
Plug Co. License No.: 3077 Plug Co. Name: JOHNSON OIL  
Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL Phone: (785) 543-6171

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls - 15 sxs gel.  
7" at 3449'. 5 1/2" liner set at 1467' cwc.  
PBTB 3394'. Fluid Level 1100'.  
Perfs 3077' - 3208'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/30/2002 1:25 PM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Allied pumped 75 sxs 60/40 pozmix - 10% gel with 250# hulls,  
followed with 15 sxs gel spacer with 250# hulls, followed with 100 sxs cement.  
Max. P.S.I. 1200#. S.I.P. 1000#.  
Hooked up to backside - instant pressure 400#.  
Note: 5 1/2" liner to 1467' cwc.

RECEIVED  
JAN 06 2003  
ROOKS COUNTY  
1/6/03

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

170

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-7-03

WV. NO. 2003061042

JAN 02 2003

JOHNSON OIL  
PHILLIPSBURG KS 67661

22-08S-19W  
NW SW NW

#1 PETERSON OWWO

site: 7-3/4 N OF ZÜRICH KS

cty: ROOKS

API 15-163-01400

contr: JOHNSON OIL

field: WEBSTER

geol:

fr  
date 08/21/2001

spd  
date 08/26/2001

drig  
comp 09/07/2001

card  
issued 12/03/2001

last  
revised 12/03/2001


ELV: 2004 GL SMP  
tops.....depth/datum  
ANH.....1405 +599  
B/ANH.....1455 +549  
TOP.....2968 -964  
HEEB.....3158 -1154  
LANS.....3183 -1179  
BKC.....3407 -1403  
PBD.....3420 -1416  
CONG.....3430 -1426  
ARB.....3449 -1445  
RTD OLD.....3458 -1454  
NO LOG

IP status:

OIL, P 3 BO & 40 BWP, LKC 3202-3244 OA, 10/18/2001  
OLD INFO: OPERATOR WAS W L HARTMAN, 1  
PETERSON, SPD 11/21/1947, 12/06/1947 10-3/4" 187 (ALT 2),  
5-1/2" 3449, OIL, P 168 BOPD, NW, ARB 3449-3458 ,  
12/17/1947(CARD ISSUED 01/09/1948)  
CONTR: UNKNOWN  
COMMENT: WAS TEMP API 15-10G-28086  
DRLR SD ZNS: 320-1170 (SH & SD)  
SALT ZN: 1640-1865 (SH, SHELLS & SALT)  
NO CORES OR TST'S

COPYRIGHT 2001  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)