

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-2957-00-00 ^R

NE 1/4 Sec. 27, T 8 S, R 19 W/E

330 feet from N 1/4 section line

1659 feet from W 1/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6520

Lease Name Kellogg Well # 1

Operator: Ad mail, Inc.
Name & Address

County Books

P.O. Box 271
Stockton, Ks 67669

Well Total Depth 3426 feet - #111.35

Conductor Pipe: Size X feet X

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Circle M. Drilling License Number 6591

Address Box 128, E. Hwy 36, Oberlin, Kansas 67749

Company to plug at: Hour: 1:26 PM Day: 24 Month: Feb. Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Gene Owens

(company name) Circle M. Drilling (phone) 913-475-3833

were: Order out 190 sx 50/50 permix 490 gal 390 cal. Cl. 8 5/8 plug. spot through drill stem w/ heavy mud between all plugs, 1st plug @ 3420 w/ 20 sx, 2nd plug @ 1350 w/ 20 sx, 3rd plug at 788 w/ 80 sx, 4th plug @ 250 w/ 40 sx 5th plug solid Bridge @ 40' w/ 10 sx, Rat hole 10 sx, Mouse hole w/ 10 sx

Signed Ken Mowry
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:00 PM, Day: 24 Month: Feb. Year: 19 83

ACTUAL PLUGGING REPORT Order out 190 sx 50/50 permix, 490 gal 390 cal. Cl. 8 5/8 plug. Spot through drill stem w/ heavy mud between all plugs. 1st plug @ 3420 w/ 20 sx, 2nd plug @ 1350 w/ 20 sx, 3rd plug at 788 w/ 80 sx, 4th plug @ 250 w/ 40 sx 5th plug solid Bridge @ 40' w/ 10 sx, Rat hole 10 sx, Mouse hole 10 sx

Remarks: Cementing done by Allied

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1983
MAR 14 1983
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 4-8-83
INV. NO. 3889-W

Signed Ken Mowry
(TECHNICIAN)