

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1962
MAR 20 1962
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: CS 1/2 NW SW Sec. 27 Twp. 8 Rge. _____ (E) _____ (W) 19

Name of Field: _____ Total Depth: 3419

I have this date completed supervision of plugging of:

Lease Name: Verveka Well No. 3

Operator's Full Name: Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor: Lynch Pipe Pulling

Address: Great Bend, Kans License No. 457

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reasons: _____

Operation Completed: Hour 6PM Day 15 Month 3 Year 62

The above well was plugged as follows:

8 5/8" 236' circulated with cement - 5 1/2" 3403' with 100 sax cement.

Filled with sand to 3390', set 4 sax cement with dump bailer, pulled

2700' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at

550', displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180',

displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge

and 10 sax cement to bottom cellar.

Mudding and cementing by Lynch Co pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 3/30/62
INV. NO. 4922-W