

15-163-04143-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 7 1962

CONSERVATION DIVISION
Wichita, Kansas

3/7/62

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks _____

Location: CE¹/₂ NE SE Sec. 28 Twp. 8 Rge. _____ (E) _____ (W) 19

Name of Field: _____ Total Depth: 3428

I have this date completed supervision of plugging of:

Lease Name: Verveka Well No. 5

Operator's Full Name: Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Ralph Lynch

Address: Great Bend, Kansas License No. 457

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 3 Month 3 Year 62

The above well was plugged as follows:

8 5/8" 256' circulated with cement - 5 1/2" 3420' with 100 sax cement.

Filled with sand to to 3410', set 4 sax cement with dump bailer - pulled 2725'

5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" - displaced 20 sax

cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement through

5 1/2" at 180', heavy mud to 35', set bridge and filled to bottom cellar with

cement.

Mudding and cementing by Lynch pump truck

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 3/16/62
INV. NO. 4646-u