

15-163-03180-00-00

70

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: NE SE SE Sec. 28 Twp. 8 Rge. (E) (W) 19

Name of Field: _____ Total Depth: 3420

I have this date completed supervision of plugging of:

Lease Name: Verveka Well No. 6

Operator's Full Name: Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Ralph Lynch

Address: Great Bend, Kans License No. 396

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: 11/29/01

CONSERVATION DIVISION
Wichita, Kansas

Operation Completed: Hour 4 PM Day 25 Month 11 Year 01

The above well was plugged as follows:

8 5/8" 241' circulated with cement - 5 1/2" 3418' with 125 sax cement.

Sand to 3400', set 5 sax cement with dump bailer, pulled 2580' 5 1/2" to

550' - circulated hole with heavy mud 22 sax Gel with 5 sax bulls -

displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced

20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax

cement to bottom cellar.

Mudding and cementing by Lynch Co pump truck.

Signed: Edon Kelly
Conservation Division Agent

Reviewed: Harold Hoesli
Field Supervisor

Remarks:

INVOICED
DATE 12/5/01
INV. NO. 4135-W