

15-163-03182-00-00

7/13/60

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1960

CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: NW NE SE Sec. 28 Twp. 8 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3480

I have this date completed supervision of plugging of:

Lease Name: Verveka Well No. 9

Operator's Full Name: Peel-Hardman

Complete Address: RR # 3 Box 144B Wichita, Kans

Plugging Contractor: Barnes & Sons

Address: Russell, Kans License No. 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7 6PM Day 6 Month 7 Year 60

The above well was plugged as follows:

8 5/8" 160' circulated with cement - 5 1/2" 3480' with 125 sax cement,
PB 3461' - perf 3440'.

Filled with sand to 3430', set 4 sax cement with dump bailer, pulled
2000' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500',
(20 sax Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to
180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 7/15/60
INV. NO. 1647u