

15-163-19144-00-01

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
 Administrator
 P. O. Box 17027
 Wichita, Kansas 67217

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 27 1972
 CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Clinton Oil Company
 Complete Address 217 N. Water Wichita, Kansas 67202
 Lease Name J. A. Stice Well No. 3
 Location C S/2 NE SW Sec. 27 Twp. 8 Rge. (E) (W) 19
 County Rooks Total Depth 3405'
 Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Rockhold Engineering
 Address Box 698 Great Bend, Kansas License No. 670
 Operation Completed: Hour 10:30 A Day 23 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 3405' 13" csg at 158' cwc 8 5/8 csg at 1394' cwc 1000 sk.
 5 1/2 csg set at 3401' cw 200 sk cmt.
 5 1/2 csg PBTD 3380' with top perf. (3063')
 Set 5 1/2 wood plug at 3000' -poured 25' sd -dumped 5 sk cmt W/dump bailer. (2940-3000)
 Cutoff and recovered 2300' of 5 1/2 csg.
 Mud to 750' -set rock & sand bridge (750-735) Dumped 3 yds readymix cem. (500-735)
 Filled with mud to 250' -set rock & sand bridge (250-235) Filled with 3 yds
 readymix cmt 235' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing
 Well Plugging Supervisor

INVOICED

DATE 12/29/72
 INV. NO. 6776-4