

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW SE SE

SEC. 27 TWP. 8 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Verveka

Operator Barnett Oil Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3382 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 165' circulated with cement - 5 1/2" at 3379' with
150 sax cement behind - Lane Wells plugsto 3224' - Perforations
at 3106' -

Filled with sand to 3150', set 4 sax cement with dump bailer,
pulled 2320' 5 1/2" - Filled hole with mud - pumped cementing plug
to 245', followed by 50 sax cement to 95', mud to 20', set
rock and cement to bottom cellar.

Mudding and cementing by Halliburton Co.

PLUGGING
FILE SEC 27 R 19
PAGE 28 OF 33

Feb 11, 1953

Eddon P. [Signature]
District Conservation Agent

Date 2-9-53