

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 1, 1967
AUG 1 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Conservation Division
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Company
Complete Address: 1425 Wichita Plaza Wichita, Kansas
Lease Name Jeffrey Well No. 1
Location SW SW NE Sec. 27 Twp. 8 Rge. 19 (E) (W) X
County Rooks Total Depth 3415'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knights Casing Plg.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3:30 P Day 31 Month 7 Year 1967

The Above well was plugged as follows:

- Total Depth 3415' 8 5/8 csg set at 270' cwc. 175 sc.
- 5 1/2 csg set at 3414' cw 100 sc cement.
- Filled with sand to 3390' and dumped 5 sc cement with dump bailer.
- Remov. 2800' of 5 1/2 csg.
- Circ. 20 sc gel at 750' thru tubing.
- Disp. 100 sc cement at 600' thru tubing.
- " 35 " " " 240' " "
- Set plg at 60' and filled to surface with 35 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/1/67
INV. NO. 6062-11

Signed: Russ F. Massey
Well Plugging Supervisor